



CITY OF DROVILLE
PLAN AND PROFILE
 OF
PROPOSED SANITARY SEWER CROSSING
 OF
FEATHER RIVER
 ON
STATE HIGHWAY BRIDGE
 ROUTE 87

City Engineer's Office
 Oroville Calif.

August 1952
 Approved
D.J. Norris RE. 914
 City Engineer.

Contractor will be required to do the following work;
 Break out present sidewalk on bridge and BRIDGE STREET.
 Break through parapet walls of abutments.
 Furnish and install saddle blocks of construction heart redwood.
 Lay C.I. Pipe from manhole to manhole.
 Furnish and install corrugated segments.
 Replace sidewalk with plant mix asphalt or class A concrete.
 In case pipe in class C concrete for 100' North from end of Bridge.
 Replace sidewalk, curb and gutter broken in BRIDGE STREET.
 All work shall comply with State of California, Department
 of Public Works, Division of Highways, Utilities Encroachment
 Permit No. 37035.
 Contractor to be paid a lump sum bid for the above work.

