



GENERAL NOTES

1. All materials and construction shall be in strict conformance with requirements of the City of Oroville, and as set forth in specifications and as shown on these plans.
2. Approval of the City of Oroville representative is required on completed work within the respective public right of way prior to backfilling trenches.

Work done without such approval shall be done at the Contractors risk. Such approval, when given shall not relieve the Contractor from the responsibility of performing the work in an acceptable manner.
3. The types, locations, sizes and/or depths of existing underground utilities as shown on these improvement plans were obtained from sources of varying reliability. The Contractor is cautioned that only actual excavation will reveal the number, types, extent, sizes, location and depth of such underground utilities. A reasonable effort has been made to locate and delineate all known underground utilities. However, Barnhart-Brown & Associates, can assume no responsibility for the completeness or accuracy of its delineation of such underground utilities nor for the existence of other buried objects or utilities which may be encountered, but which are not shown on these drawings.
4. The Contractor is hereby notified that prior to commencing construction, he is responsible for contacting the utility companies involved and verifying at the Construction Site the locations of all utilities as shown on these improvement plans, or discovered in the field. Contractor shall notify Underground Service Alert (PH. 509-421-1444) 48 hours in advance of any work.
5. The Contractor shall remove all obstructions, both above the ground and underground, except as indicated on the plans, as necessary for the construction of the proposed improvements.
6. The Contractor shall be solely and completely responsible for condition of premises on which the work is performed and for safety of all persons and property on the site, both during and outside of normal working hours, until such work is accepted by the owner.
7. Sufficient equipment shall be available to provide dust control at all times during construction operations. Areas surrounding the work shall be kept clean and returned to original conditions upon completion of this contract.
8. Where Barnhart-Brown & Associates are to provide construction stakes, the contractor shall:
 - (A) Request staking at least 24 hours in advance
 - (B) Request concrete form checks
 - (C) Preserve all stakes and monuments
9. The contractor shall, at all times, coordinate his work with that of others on the site.
10. The Contractor shall, provide construction area traffic control devices as per section of the State Standard Specifications.
11. All salvaged material shall become the property of the contractor unless otherwise noted.
12. Contractor shall be responsible for the protection of all existing monuments and other survey markers during construction. All such monuments and markers destroyed during construction shall be replaced at contractors expense.
13. The Contractor shall obtain an Encroachment Permit from the City of Oroville prior to beginning any work within the right-of-way.



APPROVED:
MIKE CRUMP
DIRECTOR PUBLIC WORKS, OROVILLE, CA
RLE 4/97, DATED

DATE	NO	REVISION	BY	APPD

FIELD BOOK
ELEVATION DATUM
BM 8\"/>

DRAWN: RB
DESIGNED: RB
CHECKED: 44B
SCALE: 1\"/>

Barnhart Brown & Associates
CIVIL ENGINEERS • LAND SURVEYORS
P.O. Box 1576 Oroville, CA 95965 916/534-1911

PLAN ^{1/2} PROFILE
SANITARY SEWER MAIN
FOR WALTER AND CARMEN BELPER

SHEET 1 OF 2 SHEETS
JOB NO 88057

PRINTED
SEP 25 1991
BARNHART BROWN & ASSOC.